

3.1. Site Improvements and Base Reach (Sta. 529+86 to Sta. 537+00) Bid Schedule

Item No.	Approx. Quantity	Unit	Item Description	Unit Price	Total Amount
000.0	-	-	CONTRACTOR ADMINISTRATION	-	-
010.0	1	Lump Sum	Mobilization (5% max.)	\$	\$
020.0	1	Lump Sum	Permit documentation / compliance	\$	\$
030.0	1	Lump Sum	General Contractor Margin	\$	\$
040.0	1	Lump Sum	Sales and Use Tax	\$	\$
050.0	1	Lump Sum	Record Document Maintenance	\$	\$
060.0	1	Lump Sum	Demobilization (3% max.)	\$	\$
100.0	-	-	SITE PREPARATION	-	-
110.0	1	Lump Sum	Access Improvement (O&M road clear and rough grade)	\$	\$
115.0	1	Lump Sum	Robinson Creek Fish Passable Culvert (incls. Restoration)	\$	\$
120.0	1	Lump Sum	Staging Site Improvements (staging site clear and rough grade)	\$	\$
130.0	1	Lump Sum	Erosion Control / SWPP Plan	\$	\$
140.0	250	Lineal Feet	Wire Fence and Gates (incls. siphon outlet and vehicle gate)	\$	\$
200.0	-	-	CANAL PIPING (Sta. 529+86 to 537+00)	-	-
211.0	700	Lineal Feet	Trench Excavation and Final Grade (incls. common borrow, compaction, and soil stabilization seeding)	\$	\$
212.0	700	Lineal Feet	Pipe Materials (incls. material and delivery)	\$	\$
213.0	700	Lineal Feet	Pipe Bedding, Install, and Haunching (incls. placement and compaction)	\$	\$
214.0	700	Lineal Feet	Trench Initial Backfill and Compaction (incls. select borrow & compaction)	\$	\$
215.0	200	Cubic Yard	Rock Excavation	\$	\$
230.0	1	Each	Telemetry Station (incls. transducer, cell comm, solar)	\$	\$
240.0	1	Each	Canal Control Structure (incls. strct & install w/ misc. metal)	\$	\$
250.0	1	Each	Replacement Irrigation Turnout, Piping, and Delivery Box (SB10.1)	\$	\$
270.0	2	Each	Pipeline to Canal Transitions (incls. both upstream & downstream)	\$	\$
TOTAL BASE REACH BID PRICE					\$

Acknowledgement that the District has no tax exemptions on this Work and the above prices include all applicable sales and use taxes.

3.2. Optional Reach Extension

The District may elect to optionally expand the baseline award based on favorable anticipated weather conditions, demonstrated productivity, and project funding availability for the following additional price per reach.

Item No.	Approx. Quantity	Unit	Item Description	Unit Price	Total Amount
000.1	-	-	CONTRACTOR ADMINISTRATION (Mob., Demob., & Permit in base)	-	-
010.1	0	Lump Sum	Mobilization (included in base)	\$0.00	\$0.00
020.1	0	Lump Sum	Permit documentation / compliance (included in base)	\$0.00	\$0.00
030.1	1	Lump Sum	General Contractor Margin	\$	\$
040.1	1	Lump Sum	Sales and Use Tax	\$	\$
050.1	1	Lump Sum	Record Document Maintenance	\$	\$
060.1	0	Lump Sum	Demobilization (included in base)	\$0.00	\$0.00
100.1	-	-	SITE PREPARATION	-	-
110.1	1	Lump Sum	Access Improvement (O&M road clear and rough grade)	\$	\$
120.1	1	Lump Sum	Staging Site Improvements (staging site clear and rough grade)	\$	\$
130.1	1	Lump Sum	Erosion Control / SWPP Plan	\$	\$
140.1	250	Lineal Feet	Wire Fence and Gates (incls. siphon outlet access control)	\$	\$
200.1	-	-	CANAL PIPING (Sta. 537+00 to 548+00)	-	-
211.1	1,100	Lineal Feet	Trench Excavation and Final Grade (incls. common borrow, compaction, and soil stabilization seeding)	\$	\$
212.1	1,100	Lineal Feet	Pipe Materials (incls. material and delivery)	\$	\$
213.1	1,100	Lineal Feet	Pipe Bedding, Install, and Haunching (incls. placement and compaction)	\$	\$
214.1	1,100	Lineal Feet	Trench Initial Backfill and Compaction (incls. select borrow & compaction)	\$	\$
215.1	400	Cubic Yard	Rock Excavation	\$	\$
220.1	1	Each	Overshot & Undershot Drains (incls. all materials and installation)	\$	\$
270.1	0	Each	Pipeline to Canal Transitions (downstream transition incl'd in base)	\$0.00	\$0.00
TOTAL OPTIONAL REACH EXTENSION BID PRICE				\$	

Acknowledgement that the District has no tax exemptions on this Work and the above prices include all applicable sales and use taxes.